



Panel OV-T 19" 2U, with telescopic pull-out,

Straight cable entry integrated 1 x 20mm + 2 x 15mm,
 Straight cable entry integrated 1 x 20mm + 1 x 25mm,

Without front panel,
 With fixing bolt and polymer nut for splice cassettes,
 1 x screw connection with lock nut M20,
 3 x fiber holder.



Dätwyler IT Infra GmbH
 Technical Support & Solution Engineering
 Auf der Roos 4-12
 65795 Hattersheim, Germany

Product name	FO lade OV-S, 19inch, 2U, with telescopic pull-out	Drawing No.	TSSE-FO-A013-V01
Article No.	41555700ZY	Version	1.0
Material	\	Drawn by	Anja Hu
Color	RAL 9005	Comments	\
Surface	\	Date	04.09.2023

The information in this document is the property of Dätwyler IT Infra GmbH and may not be reproduced or disclosed to a third party, or used for any purpose other than that for which it is supplied without a written authorization of Dätwyler IT Infra GmbH!